

INFI90 / NETWORK90 MODULES

INFI/N90 MODULES
10-June-98

<u>QTY</u>	<u>Nomenclature</u>	<u>Description</u>
1	INPPR01-232L	PLANT LOOP TO PLANT LOOP REMOTE INTERFACE, 5000 PTS INCLUDES REQUIRED MODULES, CABLES, TERMINATIONS,

DIGITAL STATIONS

1	IISAC01	ANALOG CONTROL STATION MANUAL/AUTO STATION WITH AUTOMATIC BYPASS
1	NDIS01	DIGITAL INDICATOR STATION INDICATION OF THREE VARIABLES
1	NDLS02	DIGITAL LOGIC STATION 8 PUSHBUTTON, 16 LED OPERATOR STATION
1	NLBS01	LOCAL BYPASS STATION HOLD ANALOG OUTPUT ON CIS/QRS REMOVAL

MODULAR REMOTE TERMINAL UNIT

1	IEMMU11	MODULE MOUNTING UNIT (MODULAR RTU ONLY)
1	IEPRA01	POWER SUPPLY 110/220 VAC, 60W
1	IEPRA02	REDUNDANT POWER SUPPLY 110/220 VAC, 60W
1	IEPRD01	POWER SUPPLY 24VDC
1	IEPRD02	REDUNDANT POWER SUPPLY 24VDC 60W
1	IMRAE11	8AI (IMRAI11 EXPANSION)
1	IMRAI01	8AI 4-20mA, 2AO 4-20mA, 0.1% ACCURACY